


History of original corner establishment:

The original corner was established by Daniel Chaplin on November 19, 1864, under GLO contract No. 107, as follows:

Set a stone 20" x 12" x 5" for the 1/4 section corner.



Description of corner evidence found:

The original corner stone is solidly set 4" in the ground and tipped to the west (down hill). The stone is 20" x 10" x 5" and plainly marked "1/4".

Description of monument and accessories established to perpetuate the original location of this corner:

At the up hill end of the stone, I set a 1 1/2" x 30" iron pipe 20" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe to the cap, from which:  
A 5/8" x 36" iron rod set 22" into the ground to refusal with a 3/4" brass washer, marked "PLS 1636 S26 NE", attached at ground level, bears N36°30'E, 75.8 feet.

A 5/8" x 36" iron rod set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 S26 SE", attached at ground level, bears S32°E, 55.9 feet.

A basalt stone in place, 3 1/2' x 3' x 15" high, is marked "+" on the northerly top edge, and "27" on the flat north face. The "+" bears S29°W, 103.2 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S27", attached at ground level, bears N52°W, 79.0 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 23, 1997. Magnetic declination: 20°E.

REGISTERED PROFESSIONAL LAND SURVEYOR

*Dennis L. Gaylord*

OREGON  
JULY 4, 1978  
DENNIS L. GAYLORD  
1636

Renews 6/30/97

Office of COUNTY SURVEYOR County of UMATILLA

State of OREGON, I hereby certify that the within instrument was filed in this office for record on the 23 day of February, 1997.

*David H. ...* by *Dennis L. Gaylord*  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 2-97

Rec'd By KK

No. 97-28-R