


History of original corner establishment:

The original corner was established by Daniel Chaplin on November 18, 1864, under GLO contract No. 107, as follows: Set a stone 20" x 10" x 8" for the 1/4 section corner.



Description of corner evidence found:

A basalt stone, 19" x 13" x 7", solidly set 8" into the ground and plainly marked "1/4" on the north face. A mound of stones is along the northwest side of the corner stone.

Description of monument and accessories established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in it's place a 1 1/2" x 30" iron pipe 24" into the ground surrounded by a mound of stones. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the south side of the iron pipe, from which:

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S25 NE", attached at ground level, bears N32° E, 100.2 feet.

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S36 SE", attached at ground level, bears S48° E, 80.6 feet.

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S36 SW", attached at ground level, bears S76° W, 67.0 feet.

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S25 NW", attached at ground level, bears N47° W, 66.1 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 7, 1997. Magnetic declination: 20° E.

Witnesses: Milena Gaylord
Jacqueline Franco



Office of... County of...
 State of... I hereby certify that the within instrument was filed in this office
 for record on the... day of... 19...

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 4-97
 Rec'd By RK
 No. 97-61-R

GPO-791-311