


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 3  
DIAGRAM

History of original corner establishment:

The original corner was established by Daniel Chaplin on November 21, 1864, under GLO contract No. 107, as follows:



Set stone 18" x 12" x 4" for 1/4 section corner.

Corner evidence recovered:

Found the original corner stone loosely set on the north edge of a mound of stones. The corner stone is 17" x 14" x 6" and is plainly marked "1/4" on the south face.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 22" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the northwest side of the iron pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N32°30'E, 107.6 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S33°E, 72.6 feet.

A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S22°W, 112.5 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N38°W, 158.2 feet.

The reference to the northwest is west of a farm road which runs NE-SW between the corner and the reference. This farm road is about 100 feet westerly of the corner.

I hereby certify the above corner point was perpetuated as hereon described on June 2, 1998. Magnetic declination: 18°E.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Dennis L. Gaylord*  
OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1636  
*Renews 6/30/99*

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on \_\_\_\_\_, 1998.

RECEIVED BY  
Umatilla County Surveyor  
Date 7-88  
Rec'd By KK  
No. 98-1452