


History of original corner establishment:

The original corner was established by David P. Thompson on October 4, 1864, under GLO contract Number 106, as follows:

Set stone 18" x 12" x 5" for 1/4 section corner.



Description of corner evidence found:

The original corner stone is lying on top of a mound of stones. The corner stone is 18" x 13" x 7" and is plainly marked 1/4.

Description of monument and accessories I established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in it's place a 1 1/2" x 30" iron pipe, 24" into the ground. I bury the corner stone along the west side of the iron pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached is marked as shown in the diagram above, from which: A 5/8" x 24" iron rod, set 20" into the ground with a 3/4" brass washer attached at ground level marked "PLS 1636 S34 NE", bears N26°E, 84.0 feet.

A 5/8" x 24" iron rod, set 22" into the ground with a 3/4" brass washer attached at ground level marked "PLS 1636 S3 SE", bears S80°E, 57.4 feet.

A 5/8" x 36" iron rod, set 34" into the ground with a 3/4" brass washer attached at ground level marked "PLS 1636 S3 SW", bears S54°W, 97.5 feet.

A 5/8" x 36" iron rod, set 34" into the ground with a 3/4" brass washer attached at ground level marked "PLS 1636 S34 NW", bears N80°W, 57.0 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 2, 1997. Magnetic declination: 20°E.

**REGISTERED PROFESSIONAL LAND SURVEYOR**

*Dennis L. Gaylord*

DENNIS L. GAYLORD  
1636

Office of COUNTY SURVEYOR County of UMATILLA  
 State of OREGON, I hereby certify that the within instrument was filed in this office  
 for record on the 20 day of February, 1997  
*David H. Lee* by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)

*Renews*  
*6/30/97*

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 2-97  
 Rec'd By KK  
 No. 97-19-R