


History of original corner establishment:

The original corner was established by David P. Thompson on October 5, 1864, under contract number 106, as follows:

Set stone 36" x 8" x 8" for corner to sections 35, 36, 1 & 2.



Description of corner evidence found:

Found a basalt stone, 30" x 8" x 7", lying on top of a mound of stones. The stone is coarse, but I can see chisel marks on one face near the end. There is a depression on the east side of the stone mound near the bottom end of the corner stone where the stone once stood upright.

Description of monument and accessories established to perpetuate the original location of this corner:

In the depression once occupied by the corner stone, I set a 1 1/2" x 30" iron pipe 16" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod, set 18" into the ground with a 5/8" brass washer, marked "PLS 1636 S36", attached at ground level, bears N52°E, 51.8 feet.

A 5/8" x 24" iron rod, set 20" into the ground with a 5/8" brass washer, marked "PLS 1636 S1", attached at ground level, bears S31°E, 58.6 feet.

A 3/4" x 36" aluminum rod, set 24" into the ground with a 5/8" brass washer, marked "PLS 1636 S2", attached at ground level, bears S60°W, 42.3 feet.

A 5/8" x 24" iron rod, set 20" into the ground with a 5/8" brass washer, marked "PLS 1636 S35", attached at ground level, bears N23°30'W, 51.2 feet.

I hereby certify the above corner point was perpetuated as hereon described on November 10, 1996. Magnetic declination: 20°E.

REGISTERED PROFESSIONAL LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renew 6/30/97

Office of COUNTY SURVEYOR County of UMATILLA

State of OREGON, I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by (DEPUTY)

(COUNTY OFFICIAL)

RECEIVED BY
Umatilla County Surveyor
Date 11-96
Rec'd By KK
No. 96-128-R