

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 5
DIAGRAM

History of original corner establishment:

The original corner was established by David P. Thompson on October 4, 1864, under GLO contract No. 106, as follows:

Set stone 22" x 12" x 4" for corner to sections 31, 32, 5 and 6.



Corner evidence recovered:

The original corner stone is loosely set in a large mound of stones. The corner stone is broken into several pieces, and I can see faint chisel marks on one face. I fit the pieces together and the stone is 19" x 12" x 5" in size.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe, 12" into the ground to bedrock. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone pieces to the north of the pipe and build a mound of stones around the pipe and over the brass cap, from which:

A 5/8" x 24" iron rod set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 S32", attached at ground level, bears N47°45'E, 85.4 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S5", attached at ground level, bears S45°E, 106.6 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S6", attached at ground level, bears S26°30'W, 91.8 feet.

A 5/8" x 36" iron rod set 32" into the ground with a 3/4" brass washer, marked "PLS 1636 S31", attached at ground level, bears N40°30'W, 103.4 feet.

I hereby certify the above corner point was perpetuated as hereon described on May 10, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Gaylord
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 10-98
Rec'd By KK
No. 98-112-R