

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 15  
DIAGRAM

History of original corner establishment:

The original corner was established by David P. Thompson on October 9, 1864, under GLO contract No. 106, as follows:

T2S R32E  
1/4 S34  
T3S R32E  
PLS 1636  
1999

Set post for 1/4 section corner, from which:  
A 8" fir bears N40°W, 13 links (8.58 feet).  
A 12" fir bears S5°W, 5 links (3.3 feet).

On May 27, 1882, George S. Pershin, under GLO contract No. 551, was unable to find Thompson's corner. Pershin set a basalt stone, 12" x 10" x 8", 8" into the ground, in creek bottom, marked "1/4" on north face, from which:

A 6" fir bears N17°W, 25 links (16.5 feet).  
A 12" fir bears S41°W, 41 links (27.06 feet).

Corner evidence recovered:

Pershin's original 12" fir is now a 31" white fir snag, broken off about 30 feet high. The upper blaze is healed over and partially chopped open. The lower blaze is healed. I open the upper blaze to scribes. This tree bears S41°W, 27.1 feet. The corner stone is gone, probably disturbed by logging activities. The original bearing tree to the north west is gone.

Monument and accessories established to perpetuate the original position of this corner:

At record bearing and distance from the remaining original bearing tree, I set a 1" x 30" iron pipe 25" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I build a mound of stones around the pipe to the cap, from which:

- A 12" Englemann Spruce, scribed "1/4 S34 BT", bears N53°30'E, 15.0 feet.
- A 13" Western Larch, scribed "T3S BT", bears S42°30'E, 157.2 feet.
- A 4" Englemann Spruce, scribed "T3S BT", bears S33°W, 31.8 feet.
- A 5" White Fir, scribed "1/4 S34 BT", bears N36°W, 73.4 feet.

All four new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B". The original bearing tree snag and the four new bearing trees have a "Bearing Object" sign nailed above the blazes. The spruce bearing tree to the north east has a "Witness Post" sign nailed to the back.

I hereby certify the above corner point was perpetuated as hereon described on September 3, 1999. Magnetic declination: 18°E.

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on \_\_\_\_\_, 1999.

RECEIVED BY  
 Umatilla County Surveyor  
 Date 10-99  
 Rec'd By KR  
 No. 99-213-R