

USDA-FOREST SERVICE

Index

File No. V-5

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. Section


T 2S R. 33E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND At approx. corner location, using terrain calls made to the north-south & east, found stone mound 1 ft high & 4 ft dia. at base with 16x8x4" stone lying flat in middle of mound. Visible faint notch on south and 2 notches visible on east side. Accept location of stone as true corner position based on best available evidence.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None were set originally.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on steep south slope approx. 400 ft north of bottom of draw.

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature
Donald R. [unclear]

Title

Division

Headquarters

Date

ORLS

1294

9-77

7100-52-(3-68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

In place of stone set 2 1/2"x30" galvanized pipe with brass cap stamped:

T2S	R33E
S30	S29
S31	S32

1980

OR PLS 1294

Set pipe 10" in ground with mound of stone to cap; buried the original stone alongside.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

No trees are within limits or practical dist. The steepness of terrain makes it impractical to build mound of stones for bearing objects. Use 3 natural monuments and shoot bearings to them: A Lone Tree on top of north-south ridge to the east bears N79° E. A Large Rock protruding vertically at west end of large rock outcropping on east-west ridge just south of corner bears S57° E. North end of large rock outcropping on north end of ridge running north-south lying east of corner bears N60° 30' E. Attached 54-4 sign to metal post 6 ft north of corner.

Work Done By R. C. Orton Title Party Chief Date 8-12-80 State Registration No. _____ or Agency _____

Certified Cor. Record Prepared ? (Yes) No Filed At: _____ Date _____

Witnesses:

R. Orton
L. Huntsman
D. Allen

REMARKS

Index File No.	T.	R.	M.	Tract or Surv. No.	Cor.
V-5	2S	33E			