


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Z-3

History of original corner establishment:

Nothing were originally set.



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2"x30" galvanized pipe with brass cap stamped:

Set pipe 24" in ground with mound of stone to cap.

Bearing Trees:

A Fir (Douglas) 14" in dia. bears N50°W 23.2 ft, scribed 1/4 S31 BT.
A Tamarack 12" in dia. bears N1°E 25.8 ft, scribed 1/4 S31 BT.

Attached 54-3 & 54-4 signs to all BT's. Attached brass washer stamped LS1294 to foot blaze of new BT's. Painted blazes and 6" band around all BT's. Attached 54-2 & 54-4 signs to metal post 5' east and 54-2 sign on metal post 5' north of corner.

T2S R33E
 1/4 S31
 T3S R33E
 1980
 OR PLS 1294



I hereby certify the above corner monument was established as herein described on August 20, 1980.

Witnesses: R. Orton
G. Wagoner
G. Lester
J. Anderson

Office of..... County Surveyor..... County of..... Umatilla
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... December....., 19..... 80
 David L. Greenberg..... by..... B. Hatto
 (COUNTY OFFICIAL)..... (DEPUTY)