

USDA-FOREST SERVICE

Index

File No. Z-3

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____


Cor. No. 1/4

T 2S R. 33E

R.D. Ukiah County Umatilla

Merid. Willamette N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None were originally set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None were originally set.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on steep east slope about 350' west of Pearson Creek Road.

Handwritten Signature

Title

Division
ORLS

Headquarters
1294

Date
9-77

7100-52-(3,68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2 1/2"x30" galvanized pipe with brass cap stamped:

T2S R33E
 $\frac{1}{4}$ S31

Set pipe 24" in ground with mound of stone to cap.

T3S R33E
 1980
 OR PLS 1294

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Bearing Trees:

A Fir (Douglas) 14" in dia. bears N50°W 23.2 ft, scribed 1/4 S31 BT.

A Tamarack 12" in dia. bears N1°E 26.8 ft, scribed 1/4 S31 BT.

Attached 54-3 & 54-4 signs to all BT's. Attached brass washer stamped LS1294 to foot blaze of new BT's. Painted blazes and 6" band around all BT's. Attached 54-2 & 54-4 signs to metal post 5' east and 54-2 sign on metal post 5' north of corner.

Work Done By R. C. Orton Title Party Chief Date 8-20-80 State Registration No. _____ or Agency _____

Certified Cor. Record Prepared? (Yes) No Filed At: _____ Date _____

| | |
|---|---------|
| Witnesses: R. Orton G. Wagoner G. Lester J. Anderson | REMARKS |
|---|---------|

| | | | | | | |
|----------------|----|-----|----|--------------------|------|----|
| Index File No. | T. | R. | M. | Tract or Surv. No. | Cor. | 13 |
| Z-3 | 25 | 33E | | | | |