

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 11/13/01

CORNER DESIGNATION: Z-25, Southeast Corner of Section 36, T1S., R34E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Jacob C. Cooper under GLO Contract No. 397, dated July 1, 1881. Record states: Set post, 4 1/2 ft. long, 4 ins. sq., 2 ft. in ground, on steep hillside, facing E. and 300 ft. above bottom of canyon and 400 ft. below summit, for Cor. to Tps. 1 & 2 S., R.34 and 35 E., marked: T.1S.,S.31 on N.E., R.35 E., S.6 on S.E., T.2 S., S.1 on S.W., R.34 E., S.36 on N.W. faces, with 6 notches on E. edge, from which, A pine, 8 ins. diam., brs. N.26° E., 112 lks. dist., marked T.1S., R.35 E.,S.31, B.T. No other tree in limits, raised mound of stone alongside. Corner recovered and re-monumented by Lincoln E. Wilks under special instructions dated Feb. 20, 1917. Group 29. Record states: Intersect the point for Cor. of Tps. 1 & 2S., Rs. 34 & 35 as determined by reference to the N.E. bearing tree. This point is on a steep E. slope, where it is impracticable to set an iron post, more than 6 ins. in ground; therefore, at a point 30 lks. W. of true Cor. point Set an iron post, 3 ft. long, 3 ins. diam., 24 ins. in ground, for witness Cor. to the Cor. to Tps. 1 & 2 S., Rs. 34 & 35 E., with brass cap, marked,

T1S
R34E | R35E
S36 | S31
S1 | S6
R34E | R35E
T2S
1917

and raise mound of stone, 2 ft. base, 1 1/2 ft. high, S. of post. From the true Cor. point a pine bears N 26° E, 112 lks marked T.1S., R.35E., S.31,B.T. (Old B.T.) A fir, 12 ins. diam., brs. S.17°45'W., 352 lks. dist., marked T.2S.,R.34E.,S.1,B.T. (New B.T.)

MONUMENT AND ACCESSORIES FOUND:

Found 3 1/2" brass cap on a 3" pipe 12" protruding 12" above ground level. A small mound of earth is supporting the monument. There is a small mound of stone South of the Witness Monument. Cap is marked as shown in monument marking detail.

From which:

A 18" ponderosa pine with mostly healed blaze, which was opened to expose scribing. Tree bears N 43° E, 86.2 feet from witness corner monument.

Wilkes Fir bearing tree was not observed. There are several dead down firs in the vicinity of the tree location.

MONUMENT MARKING DETAIL:

US GENERAL LAND
OFFICE SURVEY
T1S
R34E | R35E
S36 | S31 W C 30
S1 | S6
R34E | R35E
T2S
1917

NEW ACCESSORIES TO EXISTING WITNESS CORNER MONUMENT:

Due to steep terrain and few nearby trees we set 5/8" x 30" iron rebars with yellow plastic caps stamped "OPLS 1106, WA PLS 17372", as accessories to the witness corner monument:

A 5/8" x 30" iron rebar with yellow plastic cap bears N 36°E, 43.8 feet.

A 5/8" x 30" iron rebar with yellow plastic cap bears N 45°W, 37.0 feet.

A 5/8" x 30" iron rebar with yellow plastic cap bears S 36° W, 39.5 feet.

A 5/8" x 30" iron rebar with yellow plastic cap bears S 32° E, 42. 7 feet.

Attached bearing object signs to all 5/8" iron rebars. Wired "witness" sign to the witness corner monument. All rebar accessories reference the witness corner monument.

RECEIVED BY

Umatilla County Surveyor

Date 12-01

Rec'd By KR

No. 01-209-R

Attached bearing object sign to original bearing tree (18" ponderosa pine) referencing the true corner position.

LOCATION AND COMMENTS: Corner is located on steep mountainside.

STATE PLANE COORDINATE, Oregon North, NAD 83(91), International Feet:

For true corner point: N = 648384.02
E = 8718250.12

For witness monument: N = 648384.51
30 Lks West E = 8718230.33

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

1S34Z25

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

RECEIVED BY
Umatilla County Surveyor
Date 12-01
Rec'd By RF
No. 01-209-R