

Index

File No. X-Y-15

T 2S R. 34E

Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)


Tract or
Survey No. _____

Cor.
No. Sec.

R. D. La Grande County Union

N. F. Wallowa-Whitman State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. ^{FWD} 17-171

Filed At. S.O. La Grande

Object Ident. Direct

Ident. By B.B.B. RLS

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls about 50' north of track road.

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____
Agency

Signature

Barry B. Barber

Title

P. L. S.

Division

Headquarters

Sumpter

Date


11-4-80

7100-52 (3. 68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 20" in the ground and mound of stone sround to cap.



ACCESSORIES: DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which by magnetic declination of N20°E: A 13" pine bears S44°E, 34.7 ft. scribed ULRCS34CC BT. A 13" pine bears S50°W, 16.0 ft. scribed ULRCS34CC BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on steel fence post 5' east and 54-2 on steel fence post 5' south of the corner.

Work Done By B. B. Barbour Title P.L.S. Date 11-4-80 State Registration No. Or 1051
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Union County Surveyor's Date _____

REMARKS

Witnesses: Daniel Rowland
Doug Moser
Ron Gilroy