

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 11/13/01

CORNER DESIGNATION: Z-25, Southeast Corner of Section 36, T1S., R34E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Jacob C. Cooper under GLO Contract No. 397, dated July 1, 1881. Record states: Set post, 4 1/2 ft. long, 4 ins. sq., 2 ft. in ground, on steep hillside, facing E. and 300 ft. above bottom of canyon and 400 ft. below summit, for Cor. to Tps. 1 & 2 S., R.34 and 35 E., marked: T.1S.,S.31 on N.E., R.35 E., S.6 on S.E., T.2 S., S.1 on S.W., R.34 E., S.36 on N.W. faces, with 6 notches on E. edge, from which, A pine, 8 ins. diam., brs. N.26° E., 112 lks. dist., marked T.1S., R.35 E.,S.31, B.T. No other tree in limits, raised mound of stone alongside. Corner recovered and remonumented by Lincoln E. Wilks under special instructions dated Feb. 20, 1917. Group 29. Record states: Intersect the point for Cor. of Tps. 1 & 2S., Rs. 34 & 35 as determined by reference to the N.E. bearing tree. This point is on a steep E. slope, where it is impracticable to set an iron post, more than 6 ins. in ground; therefore, at a point 30 lks. W. of true Cor. point Set an iron post, 3 ft. long, 3 ins. diam., 24 ins. in ground, for witness Cor. to the Cor. to Tps. 1 & 2 S., Rs. 34 & 35 E., with brass cap, marked,

T1S  
R34E | R35E  
S36 | S31  
S1 | S6  
R34E | R35E  
T2S  
1917

and raise mound of stone, 2 ft. base, 1 1/2 ft. high, S. of post. From the true Cor. point a pine bears N 26° E, 112 lks marked T.1S., R.35E., S.31,B.T. (Old B.T.) A fir, 12 ins. diam., brs. S.17°45'W., 352 lks. dist., marked T.2S.,R.34E.,S.1,B.T. (New B.T.)

**MONUMENT AND ACCESSORIES FOUND:**

Found 3 1/2" brass cap on a 3" pipe 12" protruding 12" above ground level. A small mound of earth is supporting the monument. There is a small mound of stone South of the Witness Monument. Cap is marked as shown in monument marking detail.

From which:

A 18" ponderosa pine with mostly healed blaze, which was opened to expose scribing. Tree bears N 43° E, 86.2 feet from witness corner monument.

Wilkes Fir bearing tree was not observed. There are several dead down firs in the vicinity of the tree location.

**MONUMENT MARKING DETAIL:**

US GENERAL LAND  
OFFICE SURVEY  
T1S  
R34E | R35E  
S36 | S31 W C 30  
S1 | S6  
R34E | R35E  
T2S  
1917

**NEW ACCESSORIES TO EXISTING WITNESS CORNER MONUMENT:**

Due to steep terrain and few nearby trees we set 5/8" x 30" iron rebars with yellow plastic caps stamped "OPLS 1106, WA PLS 17372", as accessories to the witness corner monument:

A 5/8" x 30" iron rebar with yellow plastic cap bears N 36°E, 43.8 feet.

A 5/8" x 30" iron rebar with yellow plastic cap bears N 45°W, 37.0 feet.

A 5/8" x 30" iron rebar with yellow plastic cap bears S 36° W, 39.5 feet.

A 5/8" x 30" iron rebar with yellow plastic cap bears S 32° E, 42. 7 feet.

Attached bearing object signs to all 5/8" iron rebars. Wired "witness" sign to the witness corner monument. All rebar accessories reference the witness corner monument.

RECEIVED BY

Umatilla County Surveyor  
Date 12-01  
Rec'd By KR  
No. 01-209-R

Attached bearing object sign to original bearing tree (18" ponderosa pine) referencing the true corner position.

LOCATION AND COMMENTS: Corner is located on steep mountainside.

STATE PLANE COORDINATE, Oregon North, NAD 83(91), International Feet:

For true corner point: N = 648384.02  
E = 8718250.12

For witness monument: N = 648384.51  
30 Lks West E = 8718230.33

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Mark Hammersla

1S34Z25

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

RECEIVED BY  
Umatilla County Surveyor  
Date 12-01  
Rec'd By RF  
No. 01-209-R