


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. R-9

History of original corner establishment:

In 1882, under GLO Contract No. 451, Rufus S. Moore set a post 4 ft. long, 4 ins. square 24 ins. in ground for cor. to secs. 20, 21, 28 & 29 marked T2S R35E S21 on N.E., T2S R35E S20 on NW, S29 in SW and S28 on SE faces, with 2 notches on S and 4 notches on E edges from which:

- A Fir 4" in dia. bears N37°E, 33 lks. dist. marked T2S R35E S21 BT.
- A Pine 14" dia. bears S57°W 38 lks. dist. marked T2S R35E S29 BT.
- A Pine 18" dia. bears N59°W 40 lks. dist. marked T2S R35E S20 BT.
- A Fir 3" dia. bears S26°E 47 lks. dist. marked T2S R35E S28 BT.



Description of corner evidence found:

Could find no evidence of original post.

Found Ponderosa Pine stump 25" dia. 3 ft. high with visible scribing "SR3" in open upper blaze for NW BT (lower blaze is healed over). Found Douglas Fir snag 9" dia. 12 ft. tall with partially healed over and rotted blazes with portions of visible scribing for NE BT. Could find no evidence of SW or SE BT's. From found BT's measured record distance to establish a point. This point matches record bearing from both BT's very well.

Description of monument and accessories established to perpetuate the original location of this corner:

At established point set 2½"x30" galvanized pipe with brass cap stamped:
Set pipe 24" in ground with mound of stone and dirt to cap.

From which:
Original BT's:

- N.W. P. Pine stump bears N60°W, 26.4 ft. dist.
- N.E. D. Fir snag bears N35°E, 21.8 ft. dist.

T2S	R35E
S20	S21
S29	S28
PLS 1099	
1982	

New BT's:

- A Doug. Fir 17" dia. bears N29°E, 17.5 ft., scribed T2S R35E S21 BT.
- A Doug. Fir 8" dia. bears S62½°E, 49.9 ft., scribed T2S R35E S28 BT.
- A Doug. Fir 9" dia. bears N24½°W, 44.5 ft., scribed T2S R35E S20 BT.
- A Doug. Fir 21" dia. bears S40°W, 40.9 ft., scribed T2S R35E S29 BT.

Set metal post 5 ft. south of corner. Attached signs and painted trees as per Standard Specifications for Cadastral Surveys, USFS Region 6, Oct., 1979.

Corner falls on fairly level ground N45°E 100 ft. of hunters campsite and 110 ft. north of location tag and board on dead 12" P. Pine on north side of Road 2135.

Compass Declination: 18½° E Witnesses: R. Orton

I hereby certify the above described corner monument and/or accessories was established as described on Aug. 2, 1982.



Office of.....Surveyor..... County of.....Umatilla
State of.....Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 20th day of September, 1982
.....*David K. Rembert*..... by *Bethy Shatt*.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

R-9

RECEIVED BY
Umatilla County Surveyor
Date 9-82
Rec'd By BLS
No. 82-106-R

☆ GPO 799-509