


History of original corner establishment:

This corner was established by deputy surveyor Jacob C. Cooper under contract no. 397 on September 8, 1881, as follows:
 Set a post 4' long x 4" square, 2' into the ground for the corner to sections 4, 5, 32 & 33 in a mound of stone 3 1/2' at base and 18" high, (the post was marked as prescribed in the manual), from which:



- A pine 16" in diameter bears N43°E, 15 links (9.9 feet) marked T1SR37ES33BT.
- A pine 20" in diameter bears N27°W, 90 links (59.4 feet) marked T1SR37ES32BT.
- A pine 36" in diameter bears S35°W, 63 links (41.6 feet) marked T2SR37ES5BT.
- A pine 16" in diameter bears S39°E, 87 links (57.4 feet) marked T2SR37ES4BT.

Chaining west from this corner, Cooper calls at 10.00 chains: "Touch Fox's hill road on north end of bridge - a ravine, course: SE".

Description of corner evidence found:

I found a large mound of stones at the corner. From the center of the recovered mound of stones I found the following bearing tree evidence:

- A burnt stump hole bears N43°E, 9.9 ft. Nothing remains of the tree.
- A burnt stump hole bears N27°W, 59.4 ft. Nothing remains of the tree.
- A burnt stump hole bears S35°W, 41.6 ft. Nothing remains of the tree.

I also found the following evidence of subsequent perpetuation of the corner:

A 14" burnt ponderosa pine snag, with a charred location sign nailed to it facing the mound of stones, bears N46°E, 16.4 ft.

I chained west from the mound of stones and at 660 feet I came to a small creek flowing southeast at the point where an old road crosses.

Description of monument and accessories established to perpetuate the original location of this corner:

In the center of the mound of stones I set a 2 1/2" by 30" aluminum pipe, with a 2 1/2" aluminum cap attached, 27" into the ground. I raised a mound of stones around the pipe to the top of the cap. The cap is marked as shown in the diagram, above. New bearing trees:

A 24 inch diameter ponderosa pine bears N88°E, 110.9 feet scribed "T1S R37E S33 BT" on a single blaze.

A 18 inch diameter ponderosa pine bears S11°E, 185.4 feet scribed "T2S R37E S4 BT" on a single blaze.

All other trees near the corner are dead from a fire which occurred in the fall of 1986 and are currently being logged.

Both new BT's have a 3/4 inch brass washer, marked "PLS 1636", nailed flush to the base of the scribed blaze, and have "bearing tree" and "attention" signs nailed to them. The blaze is painted with red paint and a red band is painted around each tree.

I hereby certify this corner position was perpetuated as hereon described on June 7, 1988. De: 20°E. Witness: Rodney Lewis.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Dennis L. Gaylord

**OREGON
JULY 18 1928
DENNIS L. GAYLORD
1636**

Office of COUNTY SURVEYOR County of UMATILLA
 State of OREGON I hereby certify that the within instrument was filed in this office
 for record on the 30th day of June, 1988
David H. Keumbert by Kathleen Amberg
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor
 Date 6-88
 Rec'd By KA
 No. 88-40-R