

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 01/26/23.

CORNER DESIGNATION: A-11, the North Quarter corner of Section 4, Township 3 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by N.H. Gates under Contract No. 84, dated July 22, 1859. Gates set a post in earth mound. The corner point was reestablished by single proportion measurement on Survey No. S-156-C and monumented with a brass cap on galv. iron pipe monument. This corner monument has been used for subsequent surveys in the vicinity.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on iron pipe 2" above ground level with orange carsonite post 1' +/- North of monument in unfarmed brush covered area, stamped as shown in Monument Marking Detail.

MONUMENT MARKING DETAIL:

T4N R28E
1 33
4 4
T3N R28E
1980
PLS 933

MAINTAINED CORNER MONUMENT:

New accessories:

- A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 50°37'13" E, 37.24'. Wired bearing object sign to rebar.
- A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 34°59'19" E, 46.32', in East-West running fence line. Nailed bearing object sign to wood post by rebar.
- A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 28°37'49" W, 44.16', In East running fence line at railroad tie gate post. Nailed bearing object sign and Witness post sign to railroad tie.
- A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 51°24'05" W, 38.17'. Wired bearing object sign to rebar.

Courses to corner accessories are State Plane Grid bearings and distances.

LOCATION AND COMMENTS: Corner falls in unfarmed brush covered field 45' +/- Northerly of an East-West running fence line.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 771691.78
E: 8502780.64

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\3N28A-11



RENEWS: 6.30.24

24-004-C