

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 01/24/23.

CORNER DESIGNATION: E-11, the South Quarter corner of Section 4, Township 3 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by N.H. Gates under Contract No. 84, dated July 22, 1859. Gates set a post in earth mound. Survey No. S-14-B recovers a stone and sets a brass cap on galv, iron pipe monument at position of found stone in 1981.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on iron pipe 12" below ground in unfarmed CRP field with steel fence post 1'+/- North of monument, stamped as shown in Monument Marking Detail.

MONUMENT MARKING DETAIL:

T3N R28E
1/4 4/9
1981
PLS 933

MAINTAINED CORNER MONUMENT:

New accessories:

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 13°35'26" E, 65.7', at railroad tie fence corner post. Nailed bearing object sign to railroad tie.

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 08°39'14" E, 101.1', in North running fence line. Wired bearing object sign to rebar.

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 33°30'54" E, 76.7', In East running fence line. Wired bearing object sign to rebar.

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 46°57'33" E, 94.0', In East running fence line. Wired bearing object sign to rebar.

Attached Witness Post sign to steel fence post 1' +/- North of corner monument.

Courses to corner accessories are State Plane Grid bearings and distances.

LOCATION AND COMMENTS: Corner falls in unfarmed CRP field South 13° West, 65'+/- from a fence corner with fences North, East, and West.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 766325.86
E: 8502863.97

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\3N28E-11



RENEWS: 6:30:24

24-004-C