

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/22/23.

CORNER DESIGNATION: G-1, the West Quarter corner of Section 7, Township 3 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by N.H. Gates under Contract No. 84, dated July 22, 1859. Gates set a post in earth mound. The corner was reestablished by single proportion measure by Otis Gould, U.S Department of the Interior Surveyor in 1940. Gould monumented with a 2 1/2" brass cap on 1" pipe and dug pits 18"X18"X12", 3' distance, North and South of corner. Survey No. 90-49-B found the corner monument, cut it to 10" in length and reset it with cap 24" below ground. Survey No. 90-49-B also set a witness corner monument 700' East. All subsequent surveys in the area, since the Gould recovery have held this corner reestablished by Gould.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on 1" pipe buried 28" below ground in a irrigated grass circle. There is another pipe monument, lying flat, with railroad spikes below it beside the found monument. The brass cap witness corner per survey No. 90-49-B was also recovered and the course from the corner monument is noted below. The corner monument cap is stamped as shown in Monument Marking Detail.

MONUMENT MARKING DETAIL:

·1/4
S12|S7
1940

MAINTAINED CORNER MONUMENT:

New accessories:

The existing 2 1/2" brass cap witness corner from Survey No. 90-49-B bears N 89°08'17" E, 699.96'. Set steel fence post with Witness post and bearing object sign by the witness monument.
A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 00°07'17" E, 1324.82'. Nailed bearing object sign on wood post beside rebar.
A blue Deep-1 magnet buried 28" in the ground bears S 45°10'29" W, 35.56'.
An orange Deep -1 magnet bears N 52°38'51" West, 39.68'.

Buried bearing object signs with the Deep-1 magnets.

Courses to corner accessories are State Plane Grid bearings and distances.

LOCATION AND COMMENTS: The corner falls in an a irrigated grass circle.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 763624.53
E: 8489882.91

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\3N28G-1



RENEWS: 6/30/24

24-004-C