

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/20/23.

CORNER DESIGNATION: G-13, the East Quarter Corner of Section 9, Township 3 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by N.H. Gates under Contract No. 84, dated July 22, 1859. Gates set a post in earth mound. Survey No. 357, found in Record of Private Survey Books, indicates the corner area was surveyed through, but there is no call for a corner found or reestablished.

MONUMENT AND ACCESSORIES FOUND: None. I reestablished the corner point by single proportion measure between the Northeast and Southeast corners of Section 9.

MONUMENT MARKING DETAIL:

T3N R28E
1/4
S9 | S10
2023
PLS 54657

NEW MONUMENT SET:

At the position determined by survey set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe 50" in the ground. The brass cap is 20" below ground line in an area that has been farmed in the past. The corner falls about 18' North of a East-West field road and about 12' East of the East edge of a North-South field road. I set a wood fence post 1.5' +/- North of corner monument with witness sign attached. The brass cap is marked as shown in Monument Marking Detail.

New accessories:

A Silver Deep-1 magnet buried 22" below ground line bears N 53°47'11" E, 36.62'. Buried bearing object sign with the Deep-1 magnet.

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 14°30'41" E, 44.57', driven flush with ground in road bank. Did not attach bearing object sign.

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 29°35'03" W, 69.47', driven flush with the ground in road bank. Did not attach bearing object sign.

A Orange Deep-1 magnet buried 22" below ground line bears N 69°18'12" W, 46.17'. Buried bearing object sign with the Deep-1 magnet.

Courses to corner accessories are State Plane Grid bearings and distances.

LOCATION AND COMMENTS: The corner falls in the Northeast Quadrant of field roads North-South and East-West.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 763690.89
E: 8505589.31

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

3N28G-13



RENEWS: 6! 30! 24

24-004-C