

OREGON CORNER RESTORATION FORM

Section 9,10 Township 3N
County Umatilla Date: 05/21/10

Range 29E

Corner Designation: 3N29G13

Corner common to sections 9,10 T3NR29E.

_____	Condition Report Only
<u> X </u>	Not Found
<u> X </u>	Remonumented
_____	Unrecorded
<u> X </u>	Surveyed In
<u> X </u>	Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by Gates. He set a post in a mound of earth in 1859.

Monuments and Accessories Found: (Condition and Source)

None.

Diagram



Sketch

Orange Magnet •

• Silver Magnet

○ 2.5" Brass Cap

Blue Magnet •

• Pink Magnet

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N764189.71
E8538017.88
LAT - 45° 45' 18.87603" N
LON - 119° 11' 02.05038" W

Monument (s) Set (Procedures and Description)

A 1 1/2" x 30" galvanized iron pipe w/ a 2 1/2" brass cap, 23" below the surface, stamped as shown above. Set by single proportionate method.

References Set: "Deep One" magnets by Berntsen.

- A Silver magnet, 18" deep lies N 62°30' E, 20.22'.
- A Pink magnet, 18" deep lies S 6°45' W, 19.03'.
- A Blue magnet, 18" deep lies S 69°10' W, 23.87'.
- An Orange magnet, 18" deep lies N 8° W, 18.43'.

Location and Comments

The corner is North and East
0.5 miles of the Echo Golf Course.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RENEWAL DATE: 12/31/11

RECEIVED BY:

Date: 1-11
Rec'd By: RE
No. 11-12-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055