

OREGON CORNER RESTORATION FORM

Section 8,9,16,17 Township 3N
County Umatilla Date: 03/11/10

Range 29E

Corner Designation: 3N29J9

Corner common to Sections 8,9,16 and 17, T3NR29E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by N.H. Gates in 1859. He set a post in a mound of earth. Krumbain set a Brass cap by double proportion in Survey I-202-Ax. D. Haddock set another Brass cap by unknown method 37' away.


Monuments and Accessories Found: (Condition and Source)

- A 2.5" Brass Cap
- A 2.5" Brass Cap by PLS 852 lies N 75°30' E, 37.25'.
- A 5/8" Iron rebar w/opc #852 lies N 73° E, 58.60'.

Diagram



Sketch



NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N761438.59
E8532735.14

LAT - 45° 44' 52.55618555" N
LON - 119° 12' 17.16296236" W

UPRR Tracks

Monument (s) Set (Procedures and Description)

None. Replaced steel fence post (sheared by brushing activities) 1' North of monument, with Witness Post sign.

References Set:

- A 5/8" x 30" Iron rebar w/rpc #43406 lies N 15°30' W, 11.28'.
- A 5/8" x 30" Iron rebar w/rpc #43406 lies S 85°30' W, 21.50'.

Location and Comments

The corner is 0.5 miles Northeast along the Union Pacific Rail Road tracks out of Echo.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English

OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 3-10

Rec'd By: KK

No. 10-27-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11