

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 3N29L13 GEODETIC COORDINATE: NAD 83(91)

SECTION: E 1/4 S16 LAT: 45°44'26.81297" N
T. 3N., R. 29 E., W. M. LONG: 119°11'1.59481" W
UMATILLA COUNTY
OREGON

STATE PLANE CO-ORDINATES,
NAD 83-91, INT. FT. :

DATE SURVEYED: March, 1998

N: 758917.613

E: 8538136.080

SURVEYOR: DAVID L. HADDOCK
PLS 852

THETA: 0°56'0.41"

SCALE FACTOR: 0.99994443

ELEV: 689

FIRM: HADDOCK SURVEYING
P. O. BOX 1574
PENDLETON, OR 97801
(541) 276-2174

ELEV. DATUM: NGVD29

HORIZONTAL SECOND ORDER,
ORDER: CLASS I

LOCATION: From the intersection of Golf Course Rd. and Oregon Highway 320 in the City of Echo go north on Highway 320 for approximately 200 feet and turn south on the existing driveway for about 250 feet to the "Y" in the driveway. The cap is at the foot of a rail road tie on the east side of th driveway.

STATION: Station is a 2 1/4 inch brass disc on a galvanized iron pipe at the foot of a railroad tie fence corner. The cap is approximately 10 inches below the surface.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David L. Haddock

OREGON
JULY 12, 1968
DAVID L. HADDOCK
852