

**OREGON CORNER RESTORATION FORM**

Section 15,14 Township 3N  
County Umatilla Date: 05/03/10

Range 29E

Corner Designation: 3N29L17

Corner common to sections 14,15 T3NR29E.

_____	Condition Report Only
<input checked="" type="checkbox"/>	Not Found
<input checked="" type="checkbox"/>	Remonumented
_____	Unrecorded
<input checked="" type="checkbox"/>	Surveyed In
<input checked="" type="checkbox"/>	Referenced Out


**Previous Renewals / Surveys, etc.**

Originally Surveyed by Gates. He set a post in a mound of earth in 1859.


**Monuments and Accessories Found: (Condition and Source)**

None.

**Diagram**



**Sketch**



NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N759025.88  
E8543376.52

LAT - 45° 44' 27.03231" N  
LON - 119° 09' 47.68822" W

**Monument (s) Set (Procedures and Description)**

A 1 1/2" x 30" galvanized iron pipe w/ a 2 1/2" brass cap, 20" below the surface, stamped as shown above. Set by single proportion. Corner position is inside the radius of an irrigated center pivot, and appears to be just North of an electrical or water main line. The magnets to the South are in the edge of a recent excavation or maintenance activity.

**References Set:** "Deep One" magnets by Berntsen.

- An Orange magnet 24" deep lies N 49°20' W, 17.51'.
- A Silver magnet 24" deep lies N 50°15' E, 18.41'.
- A Pink magnet 24" deep lies S 51°40' E, 15.53'.
- A Blue magnet 24" deep lies S 48°30' W, 17.13'.

**Location and Comments**

The corner is 0.5 miles South from the intersection of HWY. 320 and Coppinger Road, and West 2.0 miles.

**Compass Declination**

17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
OREGON  
JANUARY 11, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

**RECEIVED BY:**

Date: 1-11  
Rec'd By: KK  
No. 11-14-R

**Firm / Agency**

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
(541) 276-2055

RENEWAL DATE: 12/31/11