

ARTIFIED RECORD OF LAND CORNER MONUMENTATION

T 3N, R 29E. , W.M.

Corner Code No. N-21


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by N.H. Gates, Deputy Surveyor, under his Contract No. 84, dated July 22, 1897.

The original notes state:

"Set post for corner to Secs 13, 14, 23 & 24 in mound of Earth & @ as per instructions."



N-21

Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Long standing fence corner with fences extending to the West and South. Corner location was verified by survey and bearing checks to remonumented corners to the South.

I accept the fence corner as the best remaining evidence of the location of the original corner and remonument as indicated below.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" G.I.P. 24" in ground and surrounded with a mound of earth, from which:

A 5/8" by 30" rebar bears N 89°W - 46.93 feet. Set a steel fence post approx. 1' from rebar with a Bearing Object sign attached.
A 5/8" by 30" rebar bears S 02 1/2°E - 5.58 feet. A Bearing Object sign was nailed to railroad tie fence post just West of rebar.
A brass washer bears N 89°W - 23.27 feet. Washer is nailed with an alum. nail to North side of a wood fence post, with a Bearing Object sign nailed to post.
A brass washer bears S 01 1/2°W - 71.18 feet. Washer is nailed with an alum. nail to the East side of a railroad tie fence post 1' above ground, with a Bearing Object sign nailed to railroad tie.

Both rebar were capped with a yellow plastic cap marked "W.R. Wells, PLS 1106".

Both brass washers are stamped "W.R. Wells, PLS 1106".

Nailed Witness Corner sign to railroad tie fence corner post near monument.

Fences go West and South.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)