

3
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 3N, R 29E . , W.M.

Corner Code No. R-19


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by N.H. Gates, Deputy Surveyor, under his Contract No. 84, dated July 22, 1859.

The originally notes states:

"Set post for 1/4 Sec. corner in mound of Earth & @ as per instructions".



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Fence corner with fences to the East and North. The remains of a old down fence extend West from the corner point.

I accept the fence corner as the best remaining evidence of the location of the original corner and remonument the corner point as indicated below.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" G.I.P. 24" in ground and surrounded with a mound of earth, from which:

A brass washer bears N 07°E - 6.33 feet. Washer is stamped "W.R. Wells, PLS 1106", and was nailed with an alum. nail 1' above ground to the East side of a railroad tie fence post with a Bearing Object sign attached.

A 5/8" by 30" rebar bears North - 54.19 feet. Bearing Object sign is attached to nearby existing steel fence post.

A 5/8" by 30" rebar bears N 87 1/2°E - 29.02 feet. Bearing Object sign is attached to nearby existing steel fence post.

A 5/8" by 30" rebar bears South - 31.01 feet. Set a steel fence post approx. 1' from rebar and attached bearing object sign.

Each rebar is capped with a yellow plastic cap marked "W.R. Wells, PLS 1106".

Nailed a Witness Corner sign to a railroad tie fence corner post near monument.

Fences go East and North and old fence posts extend West.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

★GPO-798-276

Date 6-92

Rec'd By KK

No. 92-65-C