

OREGON CORNER RESTORATION FORM

SECTION 20 TOWNSHIP 3N RANGE 29E R-5

COUNTY: UMATILLA DATE 8/91

CORNER DESIGNATION

SW Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT


PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed by Gates in 1860 under Contract #84. He set post in mound of dirt.
Staebler set a 2 1/2" B.C. on 1" Iron pipe in 1974. Co. Sur. #I-158-B.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 2 1/2" B.C. on 1" I. pipe, badly bent, in cultivated field.

MONUMENT DETAIL



SKETCH

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES From which

Center of 1321.5 ft. circle pivot Bears. N43° 23' 13" E 1801.40 ft.
Center of 532.4 ft. circle pivot Bears. N70° 34' 08"W 199.12 feet,
A 5/8" rebar with Alum. tag #951 Bears. N83° 31' 45"W 792.42 feet,
A 5/8" rebar with Alum. tag #951 Bears. S77° 08' 29"E 400.35 feet.

LOCATION & COMMENTS

From Jct. of Heppner-Echo Hwy. with Echo Meadows Rd. go South on Echo Meadows Rd. 1.2miles to a chemical wash pad. then go West .5 mile to corner in a small irr. circle.

COMPASS DEC.

FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS

NOTES

WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1871
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor

Date 10-21

Rec'd By KK

No. 91-92-P