

OREGON CORNER RESTORATION FORM

Section 29,30
County Umatilla

Township 3N
Date: 03/08/10

Range 29E

Corner Designation: 3N29T5

1/4 Corner common to sections 29,30 T3NR29E

<input type="checkbox"/>	Condition Report Only
<input checked="" type="checkbox"/>	Not Found
<input type="checkbox"/>	Remonumented
<input type="checkbox"/>	Unrecorded
<input checked="" type="checkbox"/>	Surveyed In
<input checked="" type="checkbox"/>	Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by Gates, set a post in a mound of earth, 1859.
Harris set a 1/2" Iron rebar in survey #Q-1655.


Monuments and Accessories Found: (Condition and Source)

None.

Diagram



Sketch



NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N748054.51
E8527650.53

LAT - 45° 42' 41.23032626" N
LON - 119° 13' 31.83466527" W

Monument (s) Set (Procedures and Description)

Set a 1 1/8" x 30" galvanized Iron pipe with a 2 1/2" Brass cap, stamped as shown above.
Set by single proportion between found monuments North and South one half mile.

References Set:

- A Silver magnet, 18" deep lies N 45°40' E, 16.34'. "Deep One" magnets by Bernsten.
- A Pink magnet, 18" deep lies S 16°20' E, 17.19'.
- A 5/8" x 30" Iron rebar w/rpc# 43406 lies S 63°50' W, 20.44'.
- A 5/8" x 30" Iron rebar w/rpc #43406 lies N 81° W, 18.99'.

Location and Comments

The corner is 1.5 miles South of the intersection of Hwy. 320 and Whitehouse Road, then East on a gravel road 1.0 mile.

Compass Declination
17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English

OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 3-10
Rec'd By: KK
No. 10-40-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11