

OREGON CORNER RESTORATION FORM

Section 28,29,32,33 Township 3N
County Umatilla Date: 03/11/10

Range 29E

Corner Designation: 3N29V9

Corner common to sections 28,29,32,33 T3NR29E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by Gates. He set a post in a mound of earth in 1859.
Harris set a stone and a 1/2" Iron rebar in survey #Q-1655


Monuments and Accessories Found: (Condition and Source)

Found a Bureau of Reclamation Brass cap not of record, in a mound of stone.

Diagram



Sketch



NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N745538.38
E8533020.93

LAT - 45° 42' 15.55317" N
LON - 119° 12' 16.73495" W

Monument (s) Set (Procedures and Description)

None.

References Set: "Deep One" magnets by Berntsen.

- An Orange magnet, 18" deep, lies N 44° W, 13.30'.
- A Blue magnet, 18" deep, lies N 42° E, 12.58'.
- A Pink magnet, 18" deep, lies S 35° E, 13.57'.
- A Silver magnet, 18" deep, lies S 37° W, 12.86'.

Location and Comments

The corner is South 2.2 miles South of the intersection of Snow Road and Hwy. 320., and East 0.5 miles in a field.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert Douglas English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 1-11
Rec'd By: KK
No: 11-19-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11