

OREGON CORNER RESTORATION FORM

Section 1,12
County Umatilla

Township 3N
Date: 08/20/10

Range 29E

Corner Designation: 3N29E25

Corner common to section 1,12, T3NR29E, and section 7,12, T3NR30E.

_____	Condition Report Only
_____	Not Found
_____X_____	Remonumented
_____	Unrecorded
_____X_____	Surveyed In
_____	Referenced Out

Previous Renewals / Surveys, etc.

Originally Surveyed by David P. Thompson in 1859. He set a post in a mound of earth.

Monuments and Accessories Found: (Condition and Source)

None.

Diagram



5/8" Iron rebar •

Sketch

• 5/8" Iron rebar

○ BC

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

5/8" Iron rebar •

• 5/8" Iron rebar

N767199.84
E8553755.64

LAT - 45° 45' 46.00017" N
LON - 119° 07' 19.39552" W

Monument (s) Set (Procedures and Description)

Set A 1"x30" flared galvanized iron pipe with a 2 1/2" brass cap, at the surface, by double proportionate method.

References Set:

- A 5/8" x 30" Iron rebar w/rpc #43406 lies N 58°00' W, 69.18'.
- A 5/8" x 30" Iron rebar w/rpc #43406 lies N 8°30' E, 83.06'.
- A 5/8" x 30" Iron rebar w/rpc #43406 lies S 27°30' E, 53.50'.
- A 5/8" x 30" Iron rebar w/rpc #43406 lies S 24°50' W, 33.94'.

Location and Comments

Corner is in a scab patch at the bottom of a small draw and just W of an active farm field. Approx. 3/8 mi. N of farm road.

Compass Declination
17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RENEWAL DATE: 12/31/11

RECEIVED BY:

Date: 1-11
Rec'd By: KE
No. 11-10-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055