

# CORNER RESTORATION FORM

Township 3N Range 30E Section 17 & 16 County UMATILLA

State OREGON Date 3-12-2015 Number L-9

Corner Designation : 1/4 SECTION 17 & 16


Condition Report Only  
 Not Found  
 Renewed  
 Surveyed In  
 Referenced

Previous Renewals ORIGINAL SOURCE OF CORNER

UNDER GLO CONTRACT #95 BY W. CAMPBELL DATED  
SEPTEMBER 19, 1860 SET POST  
  
Accessories Found:  
NONE

## MONUMENT DETAIL

Found  Set



BASIS OF BEARINGS, NAD 83/91 OREGON STATE PLANE COORDINATES NORTH ZONE:

NORTHING: 759360.611  
 EASTING: 8565152.496

### Monument & Accessories Set (Procedure and Description)

- SET 2 1/2" BRASS CAP ON 1 1/4"x30" PIPE 2" BELOW DRIVEWAY GRADE PLACED WHITE TIN PROTECTOR OVER BRASS CAP.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE, N54°16'E 61.90'.
- SET PK & 1-1/2" WASHER MARKED PLS 61420 IN 8" TREATED ROUND POST, S50°45'E 21.07', WITH BEARING OBJECT SIGN ON THE ROUND POST.
- SET PK & 1-1/2" WASHER MARKED PLS 61420 IN 8" TREATED ROUND POST, S37°53'W 24.84' WITH BEARING OBJECT SIGN ON THE ROUND POST.
- SET PK & 1-1/2" WASHER MARKED PLS 61420 IN RAILROAD TIE POST, S86°14'W 70.78'.

<p style="text-align: center;"><b>Sketch of Monument, Accessories and General Area</b></p> <p>                 BARN                  CONCRETE PAD                  DRIVEWAY                  EX. FENCE                  PASTURE                  DRAINAGE SWALE                  LOADING RAMP                  4.5' CMP                  N54°16'E 61.90'                  S50°45'E 21.07'                  S37°53'W 24.84'                  S86°14'W 70.78'             </p>	<div style="border: 1px solid black; padding: 5px; text-align: center;"> <b>REGISTERED PROFESSIONAL LAND SURVEYOR</b> </div> <div style="border: 1px solid black; padding: 5px; text-align: center; margin-top: 10px;">                  OREGON                  MAY 10, 2011  <b>LANCE CLARK KING</b>                  61420             </div> <div style="border: 1px solid black; padding: 5px; text-align: center; margin-top: 10px;"> <b>RENEWS: 6/30/2015</b> </div> <div style="border: 1px solid black; padding: 5px; margin-top: 10px;">                 Agency:                  CK3, LLC                  945 W. ORCHARD                  HERMISTON OREGON 97838                  OFFICE: 541-567-2345                  FAX: 541-567-2305                  WEB: CK3LLC.NET                  Field Book # 0-289             </div> <div style="border: 1px solid black; padding: 5px; margin-top: 10px;">                 COUNTY SURVEYOR RECORDING INFO                  Received <u>Day Robert</u>                  Filed <u>6/12/2015</u>                  Survey No. <u>15-050-C</u>                  Drawing No. <u>C-853</u>                  Index No. <u>L-9</u> </div>
--	--