

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 11/20/12

CORNER DESIGNATION: R-15, The South Quarter Corner of Section 22, Township 3 North, Range 30 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by William B. Campbell, Deputy Surveyor, under contract No. 95, dated September 19, 1860. Notes State: Set a post for quarter section corner, drove charred stake as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Held the intersection of farmed field lines extending North, East, and West as the best remaining evidence of the original corner.

### MONUMENT MARKING DETAIL:

T3N R30E

1 S22

4 S27

2012

PLS 54657

MONUMENT SET: At the corner point set a 2 3/8" dia. brass cap on a 1 1/4"x30" galvanized iron pipe with the top of the cap flush with the ground surface. Monument marked as shown in "Monument Marking Detail".

### From which:

A silver Deep-1 magnet buried 20" below ground level bears North 52° East, 28.9 feet.

A blue Deep-1 magnet buried 20" below ground level bears South 36° East, 26.8 feet.

A orange Deep-1 magnet buried 20" below ground level bears South 39° West, 27.3 feet.

A orange Deep-1 magnet buried 20" below ground level bears North 29 1/2° West, 24.4 feet.

Buried bearing object signs with magnets.

LOCATION AND COMMENTS: Corner is located in a farmed field with field lines extending North, East, and West.

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

/3N30R15

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Jason M. Wells*  
OREGON  
NOVEMBER 29, 2010  
JASON M. WELLS  
54657PLS

RENEWS: 6-30-14

**RECEIVED BY**

Umatilla County Surveyor

Date: 12/6/12

Rec'd By: S. Ows

No.: 12-154-B