

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 05/09/01.

CORNER DESIGNATION: V-13, The Northwest corner of Section 34, Township 3 North, Range 30 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by William B. Campbell, Deputy Surveyor, under Contract No. 95 dated September 19, 1860. Notes state: Set a post for corners to 27, 28, 33, and 34. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. I held the intersection of Temple Road running East-West with field lines extending North and South as the best remaining evidence of the original corner location.

MONUMENT MARKING DETAIL:

T3N R30E  
S28|S27  
S33|S34  
2001  
PLS 1106

MONUMENT SET: Set a 2 3/8" diameter brass cap on a 1 1/4"x30" galvanized iron pipe with brass cap 8" below gravel road surface. Cap is marked as shown in "Monument Marking Detail".

New accessories:

A silver Deep-1 magnet buried 20" below ground in farmed field bears North 43 1/2° East, 37.4 feet.

A 5/8"x24" iron rebar with 1 1/4" yellow plastic cap marked "ORPLS 1106 WAPLS 17372", 2" above ground level in road bank bears South 83° East, 156.7 feet. Accessory rebar is located within 1 foot of Umatilla County mile post 2 sign on Temple road. Set steel fence post with witness post sign attached by accessory.

A blue Deep-1 magnet buried 20" below ground in farmed field bears South 49° East, 29.0 feet. A orange Deep-1 magnet buried 20" below ground in farmed field bears North 37° West, 31.4 feet.

Buried bearing object signs with all Deep-1 magnets. Attached bearing object sign to iron rebar accessory.

LOCATION AND COMMENTS: Corner is located 8" below Temple Road with field line extending South. This certificate is recorded in 2009, because the 2001 certificate for corner monumentation was not found in County Survey Records. In 2001, there was a field line extending North from the corner point. That field line does not exist in 2009.

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\3N30V13

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-10*

RECEIVED BY

Umatilla County Surveyor

Date 2-07

Rec'd By JK

No. 19-31-2