

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 3/31/15

CORNER DESIGNATION: The North One-Quarter Corner of Section 3, Township 3 North, Range 31 East, A-15.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner. Corner re-established by Dave Krumbein on Survey M-108-B, dated 1976, at fence corner. Corner monumented with a brass cap monument..

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap 6" below ground with wood and steel fence posts, 1' North with witness sign attached. Monument marked as shown in "Monument Marking Detail".

## MONUMENT MARKING DETAIL:

T4N R31E  
S1 S34  
S4 S3  
T3N  
PLS 933 1976

## New Accessories:

- A silver deep-1 magnet buried 20" in the ground, bears North 50° East, 34.7 feet.
- A pink deep-1 magnet, buried 20" in the ground, bears South 49° East, 35.7 feet.
- A blue deep-1 magnet, buried 20" in the ground, bears South 52° West, 35.0 feet.
- An orange deep-1 magnet buried 20" in the ground, bears North 43° West, 35.2 feet.
- Buried bearing object tags with magnets.

LOCATION AND COMMENTS: At a field berm intersection with berms North, South, and East.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 773241.94  
E = 8604626.05

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy  
/3N31A15



RENEWS: 6-30-16

15-052-c