

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 4/2/15.

CORNER DESIGNATION: The Northwest Corner of Section 1, Township 3 North, Range 31 East, A-21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instructions for corner to secs 1, 2, 35 & 36. In Survey No. M-108-B, in 1976, Dave Krumbein accepted an existing fence corner and remonumented with a brass cap monument.

MONUMENT AND ACCESSORIES FOUND: Found bent 1 1/4" x 30" galvanized iron pipe without a brass cap. Tied straight position of bent pipe.

MONUMENT MARKING DETAIL:

T4N R31E  
S35|S36  
S2|S1  
T3N  
2015  
PLS 54657

MONUMENT SET:

Remonumented bent pipe with a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground level, at the straight position of the found bent pipe.

New Accessories:

- A silver deep-1 magnet, buried 20" in the ground, bears North 65° East, 46.6 feet.
- A pink deep-1 magnet, buried 20" in the ground, bears South 51° East, 45.9 feet.
- A blue deep-1 magnet, buried 20" in the ground, bears South 55° West, 40.8 feet.
- An orange deep-1 magnet, buried 20" in the ground, bears North 41° West, 34.7 feet.

Buried bearing object tags with magnets. Set steel fence post with witness post sign 1 foot South of monument

LOCATION AND COMMENTS: At rounded field corner with berms North and West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:


N = 773241.06  
E = 8612559.61

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

/3N31A21



RENEWS: 6-30-16

15-052-c