

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/09/15

CORNER DESIGNATION: The North One-Quarter Corner of Section 11, Township 3 North, Range 31 East, E-19

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D. S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1 S2
4 S11
2015
PLS 54657

MONUMENT SET:

Re-established corner on parallel of latitude between the Northwest and Northeast corners of Section 11. A distinct North-South field berm was held for departure. At re-established corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, 20" below ground level, stamped as shown in "Monument Marking Detail".

From which:

A silver deep-1 magnet, buried 20" in the ground, bears North 50° East, 39.0 feet.
A pink deep-1 magnet, buried 20" in the ground, bears South 49° East, 39.7 feet.
A blue deep-1 magnet, buried 20" in the ground, bears South 38° West, 33.6 feet.
An orange deep-1 magnet, buried 20" in the ground, bears North 49° West, 30.8 feet.
Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Corner located in a North/South field berm, in CRP field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 768011.19
E = 8609934.80

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

/3N31E19



15-052-c

RENEWS: 6-30-16