

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 5/5/15

CORNER DESIGNATION: The North One-Quarter Corner of Section 8, Township 3 North, Range 31 East, E-7.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1 S5
4 S8
2015
PLS 54657

MONUMENT SET: No physical features remain, falls in CRP field. Reestablished corner by single proportion measure on the parallel of latitude using the Payne record and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 20" below ground surface, stamped as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, 20" below ground level, bears North 45° East, 31.9 feet.
- A pink deep-1 magnet, 20" below ground level, bears South 36° East, 38.2 feet.
- A blue deep-1 magnet, 20" below ground level, bears South 35° West, 34.4 feet.
- An orange deep-1 magnet, 20" below ground level, bears North 53° West, 36.2 feet.

Buried bearing object tags with the magnets.

LOCATION AND COMMENTS: At calculated point in CRP field, with no features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 767932.28
E = 8594105.12

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East
Witnesses: Jason Wells, PLS
Dean Roy

Surveyor's Seal

/3N31E7



15-052-c

RENEWS: 6-30-16