

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/1/15

CORNER DESIGNATION: The West One-Quarter Corner of Section 10, Township 3 North, Range 31 East, G-13.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1/4
S9 | S10
2015
PLS 54657

MONUMENT SET:

Held the intersection of field berms East-West and North as best remaining evidence of the original corner location and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 16" below ground level, stamped as shown in "Monument Marking Detail".

From which:

A silver deep-1 magnet, buried 20" in the ground, bears North 38° East, 39.3 feet.

A pink deep-1 magnet, buried 20" in the ground, bears South 43° East, 33.0 feet.

A blue deep-1 magnet, buried 20" in the ground, bears South 50° West, 36.4 feet.

An orange deep-1 magnet, buried 20" in the ground, bears North 59° West, 29.9 feet.

Buried bearing object tags with magnets. Nailed witness sign to 4" x 4" pressure treated post, 2 feet North of monument.

LOCATION AND COMMENTS: At the point of field berms North, East and West. Approximately 6 feet South of the center of a bird guzzler roof.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 765290.33

E = 8602052.25

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

/3N31G13



15-052-c

RENEWS: 6-30-16