

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/08/15

CORNER DESIGNATION: The North One-Quarter Corner of Section 15, Township 3 North, Range 31 East, J-15.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1 S10
4 S15
2015
PLS 54657

MONUMENT SET:

Re-established corner at mid-point between the Northwest and Northeast corners of Section 15 holding East-West field berm for latitude and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground level, stamped as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, 20" below ground level, bears North 47° East, 45.5 feet.
- An orange deep-1 magnet, 20" below ground level, bears North 31° East, 32.4 feet.
- A blue deep-1 magnet, 20" below ground level, bears South 45° West, 26.9 feet.
- A 5/8" x 24" rebar rod with a 1 1/4" purple plastic cap stamped "Wells Surveying PLS 54657", 2" above ground level, on South hill slope, bears South 62° East, 35.2 feet, (set wood fence post with witness sign 1.0 feet East of rebar).
- Buried bearing object tags with magnets. Nailed bearing object tag to fence post.

LOCATION AND COMMENTS: Corner falls in a East-West field berm with jogged field line extending North, 16' East of corner and field berm extending South, 9 feet West of Corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 762670.26
E = 8604761.49

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

/3N31J15

15-052-C



RENEWS: 6-30-16