

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla    DATE: 04/13/15

CORNER DESIGNATION: The Northwest Corner of Section 16, Township 3 North, Range 31 East, J-9.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instructions for corner to secs 8, 9, 16 & 17.

MONUMENT AND ACCESSORIES FOUND: None

MONUMENT MARKING DETAIL:

T3N R31E  
S8|S9  
S17|S16  
2015  
PLS 54657

MONUMENT SET:

Re-established corner by double proportionate measurement from one-quarter section corners North, South, East and West and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground level, marked as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, buried 20" in the ground, bears North 35° East, 24.9 feet.
- A pink deep-1 magnet, buried 20" in the ground, bears South 49° East, 30.0 feet.
- A blue deep-1 magnet, buried 20" in the ground, bears South 56° West, 30.2 feet.
- An orange deep-1 magnet, buried 20" in the ground, bears North 51° West, 38.0 feet.

Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Corner location in a CRP field without features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 762644.95  
E = 8596810.41

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East                      Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

/3N31J9



15-052-C

RENEWS: 6-30-16