

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/7/15

CORNER DESIGNATION: The West One-Quarter Corner of Section 14, Township 3 North, Range 31 East, L-17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec post. A 1/2" rebar was established for the corner point in Survey No. Q-520-A, although the 1/2" rebar is not called the 1/4 corner on that survey. The 1/2" rebar was recovered on Survey no. 97-247-B.

MONUMENT AND ACCESSORIES FOUND: Found nail with whisker at straight position of bent 1/2" rebar from Survey No. Q-520-A, 14" below ground level at projection of centerline of Peebler Road from the West and 10 feet +/- East of the centerline of improved portion of Cresswell Road extending North-South.

## MONUMENT MARKING DETAIL:

T3N R31E  
1/4  
S15|S14  
2015  
PLS 54657

## MONUMENT SET:

At the straight position of the found 1/2" rebar from Survey No. Q-520-A, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 10" below ground level, stamped as shown in "Monument Marking Detail".

From which:

A 5/8" x 24" rebar rod with a 1 1/4" blue plastic cap stamped "Wells Surveying, PLS 54657", 1" above ground level, 1.0 feet West of UECA pole #140400, bears Grid Azimuth 247°48', 55.9 feet.

A 5/8" x 24" rebar with a 1 1/4" blue plastic cap stamped "Wells Surveying, PLS 54657", 2 inches above ground level in a fence line, bears Grid Azimuth 206°38', 23.0 feet.

A 5/8" x 24" rebar with a 1 1/4" blue plastic cap stamped "Wells Surveying, PLS 54657", at fence corner, 1.0 feet East of post, bears Grid Azimuth 190°54', 56.1 feet.

A 5/8" x 24" rebar with a 1 1/4" blue plastic cap stamped "Wells Surveying, PLS 54657", in fence line, bears Grid Azimuth 131°30', 32.9 feet.

Attached bearing object signs to all rebars and power pole at wood fence corner post.

LOCATION AND COMMENTS: At projection of centerline of Peebler Road from the West and 10' +/- East of the centerline of improved Cresswell Road North-South.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 760057.17

E = 8607451.11

FIRM: Wells Surveying

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

/3N31L17



15-052-C

RENEWS: 6-30-16