

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/19/06

CORNER DESIGNATION: 3N31, N-15, The North One-Quarter Corner of Section 22.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1 S15
4 S22
2006
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the reestablished Northwest and Northeast corners of Section 22. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 35° East, 33.3 feet.
 - A blue Deep-1 magnet buried 22" below ground level bears South 33 1/2° East, 36.8 feet.
 - A purple Deep-1 magnet buried 22" below ground level bears South 39 1/2° West, 38.1 feet.
 - An orange Deep-1 magnet buried 22" below ground level bears North 41° West, 36.4 feet.
- Buried bearing object signs with magnets.

LOCATION AND COMMENTS: Corner is located in a East-West field berm between field lines.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 757356.76
E = 8604849.12

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31N15

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

11-41-2-C