

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/25/06

CORNER DESIGNATION: 3N31, N-5, The Southwest Corner of Section 17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for corner to Secs. 17 & 18, 19 & 20.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
S18/S17
S19/S20
2006
PLS 1106

MONUMENT SET:

Re-established corner by double proportionate measure, holding intersection of centerline of Peebler Road with field line North and reestablished Southwest corner of Section 20 for latitude and reestablished North one-quarter corner of Section 18 and North-South field line through the Northeast corner of Section 20 for departure. At reestablished corner point, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 24" below ground level bears North 47° East, 37.9 feet.
 - A blue Deep-1 magnet buried 24" below ground level bears South 33 1/2° East, 37.4 feet.
 - A purple Deep-1 magnet buried 24" below ground level bears South 49 1/2° West, 43.8 feet.
 - A orange Deep-1 magnet buried 24" below ground level bears North 40 1/2° West, 39.8 feet.
- Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located 6' South of a poorly defined field line extending East-West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 757274.66
E = 8591659.06

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31N5

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08