

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/20/06

CORNER DESIGNATION: 3N31, P-13, The West One-Quarter Corner of Section 22.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for qr. section corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1
4
S21 | S22
2006
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the reestablished Northeast and Southeast corners of Section 21. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 12" below gravel road surface. Monument marked as shown in monument marking detail.

From which:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 11° East, 33.3 feet

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 07° East, 34.9 feet

A purple Deep-1 magnet buried 22" below ground level bears South 51 1/2° West, 39.6 feet.

An orange Deep-1 magnet buried 22" below ground level bears North 43 1/2° West, 42.4 feet.

Attached bearing object signs to rebar accessories and buried bearing object signs with magnets.

Set steel fence post with witness sign in road bank 5 feet East of corner.

LOCATION AND COMMENTS: Corner is located 7 feet East of the visual centerline of Barnhart Road. There are no features East or West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 754671.33

E = 8602241.20

FIRM: William R. Wells, PLS

P.O. Box 1696


Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31P13



William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

DL-462-C