

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/12/06

CORNER DESIGNATION: 3N31, P-21, The West One-Quarter Corner of Section 24.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for qr. sec. corner.

MONUMENT AND ACCESSORIES FOUND: None. Accepted intersection of field lines extending South and East, marked by a large pole, as best remaining evidence of the original corner position.

MONUMENT MARKING DETAIL:

T3N R31E
1
4
S23 | S24
2006
PLS 1106

MONUMENT SET:

At a point just East of the pole, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with top flush with ground and placed stones around East side of monument. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 44° East, 33.1 feet.
 - A blue Deep-1 magnet buried 22" below ground level bears South 38 1/2° East, 36.5 feet.
 - A purple Deep-1 magnet buried 22" below ground level bears South 42 1/2° West, 36.3 feet.
 - An orange Deep-1 magnet buried 22" below ground level bears North 31 1/2° West, 34.6 feet.
- Buried bearing object signs with all magnets. Attached witness sign to pole just East of the monument.

LOCATION AND COMMENTS: Corner is located in a farmed field at the intersections of field berms or lines extending South and East.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 754725.26
E = 8612817.59

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31P21



Will. R. Wells



renews 6-30-08