

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/25/06

CORNER DESIGNATION: 3N31, P-5, The West One-Quarter Corner of Section 20.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1
4
S19 | S20
2006
PLS 1106

MONUMENT SET:

Re-established corner position by single proportionate measure midway between reestablished Northeast and Southeast corners of section 19. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 38 1/2° East, 37.0 feet
 - A blue Deep-1 magnet buried 22" below ground level bears South 35° East, 37.2 feet.
 - A purple Deep-1 magnet buried 22" below ground level bears South 42 1/2° West, 35.4 feet.
 - An orange Deep-1 magnet buried 22" below ground level bears North 34 1/2° West, 32.2 feet.
- Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located in an actively farmed field. There are no nearby features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 754608.86
E = 8591688.76

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31P5

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

06-462-C