

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 01/18/06

CORNER DESIGNATION: 3N31, R-1, The Northwest Corner of Section 30.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David P. Thompson, under Contract No. 81, dated July 8, 1859. Record states: Set post for corner to Secs. 24, 25, 19 & 30 and built a mound of earth with pits, trench & c., as per instructions. Original evidence of this corner was recovered by Willard Bradley in Survey recorded in Book 2, Page 270. Bradley perpetuated the corner with a stone with "+" and 2 marks on South side and a iron spindle under the stone. Steve Haddock, in Survey No. 05-111-C, recovered the forged spindle.

MONUMENT AND ACCESSORIES FOUND: Found a 7/8" outside diameter pipe 15" long with forged point over the top of a "U" shaped buggy spindle, the top of the pipe being slightly bent and buried 12" below gravel road surface. We did not find Bradley's stone.

MONUMENT MARKING DETAIL:

T3N  
R30E R31E  
S24|S19  
S25|S30  
2006  
PLS 1106

MONUMENT SET: At position of pipe with forged point, I set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe, with cap 10" below the gravel road surface. Marked as shown in Monument Marking Detail.

A 3/4" brass washer stamped "PLS 1106" 1 foot above ground in UECA power pole No. 190000 bears North 56° East, 14.3 feet. Attached witness sign to this power pole.

A 3/4" brass washer stamped "PLS 1106" 1 foot above ground in UECA power pole No. 190001 bears South 87° East, 55.7 feet.

A 3/4" brass washer stamped "PLS 1106" 1 foot above ground in UECA power pole No. 300900 bears South 04° East, 129.4 feet.

A 3/4" brass washer stamped "PLS 1106" 1.5 feet above ground in meter pole bears North 39° West, 34.9 feet.

Attached bearing object signs to all power poles.

LOCATION AND COMMENTS:

Corner is set in the centerline of Yokum road running South, 3 feet West of the East edge of a gravel lane running North, and about 20 feet North of the centerline of Yoakum Road running East. Corner is 4 feet North of a fence on the North side of Yoakum Road running East.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 751958.60  
E = 8586261.11

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31R1

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-08*