

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/12/06

CORNER DESIGNATION: 3N31, V-21, The Southeast Corner of Section 26.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally set by D. S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for corner to Secs. 25 & 26, 35 & 36.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
S26|S25
S35|S36
2006
PLS 1106

MONUMENT SET:

Reestablished corner position holding East-West field berm for latitude, and proportioned record departure between reestablished corners at the Southwest corner of Section 27 and Southeast corner of Section 25. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 24" below ground level bears North 48° East, 34.9 feet.
 - A blue Deep-1 magnet buried 24" below ground level bears South 28 1/2° East, 36.9 feet.
 - A purple Deep-1 magnet buried 24" below ground level bears South 49 1/2° West, 39.1 feet.
 - An orange Deep-1 magnet buried 24" below ground level bears North 37 1/2° West, 34.1 feet.
- Set steel fence post with witness sign attached 1 foot West of monument. Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located in a East-West field line in a farmed field, 125' +/- West of a small draw running North. No other features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 746776.27
E = 8612926.07

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31V21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08