

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/25/06

CORNER DESIGNATION: 3N31, V-7, The South One-Quarter Corner of Section 29.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E  
1 S29  
4 S32  
2006  
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the reestablished Southwest and Southeast corners of Section 29. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 60° East, 42.4 feet.
  - A blue Deep-1 magnet buried 22" below ground level bears South 32 1/2° East, 34.6 feet.
  - A purple Deep-1 magnet buried 22" below ground level bears South 61 1/2° West, 37.3 feet.
  - An orange Deep-1 magnet buried 22" below ground level bears North 27 1/2° West, 50.2 feet.
- Buried bearing object signs with magnets.

LOCATION AND COMMENTS: Corner is located in a CRP field 20'+- South of a field line extending North.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 746683.38  
E = 8594440.44

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31V7

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

renews 6-30-08