

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/04/06

CORNER DESIGNATION: 3N31, X-13, The West One-Quarter Corner of Section 34.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1/4
S33 | S34
2006
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the reestablished Northeast and Southeast corners of Section 33. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 12" below gravel road surface. Monument marked as shown in monument marking detail.

From which:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 12° West, 60.5 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 41° West, 25.9 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 49 1/2° West, 23.4 feet. Set steel fence post with witness sign attached by this accessory.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 19 1/2° West, 59.0 feet.

Attached bearing object signs to iron rebar accessories.

LOCATION AND COMMENTS: Corner is located 1 foot West of the visual centerline of Barnhart Road.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 744061.08
E = 8602380.98

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31X13



William R. Wells



renews 6-30-08