

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/12/06

CORNER DESIGNATION: 3N31, X-21, The East One-Quarter Corner of Section 35.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E  
1/4  
S35 | S36  
2006  
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the reestablished Northeast and Southeast corners of Section 35. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground surface. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 21° East, 28.6 feet.
  - A blue Deep-1 magnet buried 22" below ground level bears South 42 1/2° East, 32.4 feet.
  - A purple Deep-1 magnet buried 22" below ground level bears South 58° West, 38.6 feet.
  - An orange Deep-1 magnet buried 22" below ground level bears North 49° West, 40.1 feet.
- Buried bearing object signs with all rebar accessories.

LOCATION AND COMMENTS: Corner is located in a farmed field with no features nearby.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 744117.13  
E = 8612962.11

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31X21

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-08*